

51456

OFFICE OF
India Affairs
Rec. JUL 30

1904

116 8/7 78/187

Indian Indus. School,
Carlisle, Pa., July 29, 1904.

W. A. Mercer, Capt. & Supt.

Submits under another cover plans
and specifications for 3rd story
to Small Boys' Quarters, and asks
authority to advertise and enter-
into contract.

Amended estimate of cost is
\$5795.

or Enc.

Trans. to E Aug. 7, 1904

Encl. #1 - in Draft. Div.

Misc. drawn

*File ✓
Shawley
J*



Department of the Interior,

INDIAN INDUSTRIAL SCHOOL,

OFFICE OF SUPERINTENDENT,

Carlisle, Pa., July 29, 1904, 190

To The Honorable,

The Commissioner of Indian Affairs,


Washington, D. C.

Sir :

Referring to my letter of the 26th instant with regard to an additional story to the Small Boys' Quarters, I have the honor to transmit under another cover, a copy of the plans and specifications that were to have been sent at that time, but were inadvertently omitted. I also find it necessary to revise the estimate of cost submitted in the previous letter referred to, as the carpenter informs me that certain items were omitted from the original estimate of May 20th. The estimated cost now is \$5,795.00.

I respectfully renew my request to advertise for bids for this addition and to enter into contract with the lowest responsible bidder.

Very respectfully,



Captain 7th Cavalry, Supt

E.A.A.

P.

51456

Indian Office,

1904

Incl. No. /

-2-

The ceiling of the porch shall be of yellow pine 3/4" thick
 X 8" face, beaded, planed and grooved, and have 2 trap doors fitted
 with covers. Two trap doors shall also be made on the roof of the
 building, as at present.

All labor performed shall be subject to the inspection of the
 Superintendent and any other persons appointed by him to assist in
 the same, and he shall have the power to require the discharge of any
 workman who does not perform his duties in a satisfactory manner.

The building shall be completed within 75 days after notice of
 approval of the contract.

SPECIFICATIONS FOR A THIRD STORY ON THE SMALL BOYS' QUARTERS,
U. S. INDIAN SCHOOL, CARLISLE? PENNSYLVANIA.

The walls shall be of brick 9" thick and of sufficient height to make the ceilings 9' clear. The construction and finish shall conform in all respects to the present building. All new material used is to be of first class quality, subject also to inspection by the Superintendent, whose judgment shall be final on any disputed points.

The walls shall have 2" x 4" scantling laid in at intervals of 3' and furred with 1" x 2-1/2" strips 16" centre to centre.

All partitions shall be made of 3" x 4" hemlock set 16" centre to centre, with closets as shown on the drawing, having 2" x 4" studing with 2 dressed 1" board partitions dividing the space into 3 equal parts, furnished with one shelf and 12 heavy iron hooks. Each closet shall be furnished with 3 white pine doors 18" wide, 1-1/4" thick and 6' 10" high, 5-panel, fitted with approved locks and hinges.

The two stairways shall be continued to the third floor, of the same construction and finish as those on the lower floors.

The roof shall be covered with sheeting laid tight, over which will be placed a standing seam tin roof, well soldered and fastened and finished with two coats of mineral paint of approved quality. The contractor may use as much of the old material as in the judgment of the Superintendent is suitable for the purpose. All new tin shall be I X charcoal, 14" x 28".

All woodwork outside and inside shall be covered with two coats best quality lead paint. The plastering shall be hair mortar, two coats of brown and one finishing coat of best white York lime; the first brown coat to be broomed and dry before the second is applied.

The floor shall be of 1" yellow pine, 3" face, free from sap, loose knots and shakes.

The fourth tier of joists shall be 3" x 8" bricked in, laid 16" centre to centre with 3 rows of bridging.

The ceiling of the porch shall be of yellow pine 3/4" thick x 3" face, beaded, plowed and grooved, and have 2 trap doors fitted with covers. Two trap doors shall also be made on the roof of the building, as at present.

All labor performed shall be subject to the inspection of the Superintendent and any other persons appointed by him to assist in the same, and he shall have the power to require the discharge of any workman who does not perform his duties in a satisfactory manner.

The building shall be completed within 75 days after notice of approval of the contract.